

Date 01/18/22

## **Addendum # 1 to Bid 002519**

### **AHSON Lecture Hall A Audio Visual Upgrade**

Change the above referenced Invitation to Bid to agree with this addendum.  
LSU Health Sciences Center will reject any proposal which does not acknowledge this addendum.  
Acknowledge by including a signed copy of this addendum with your bid.

#### **Bid Questions:**

Q. Does the Huddle Pod Air2 Duo connect directly to the OFE PC?

A. No, it only needs to be provided by the bidder

Q. Do we provide LSUHSC LAN connections for all AV devices such as NVX devices, CP4N, and Core 110f? If so, where is the nearest IT Closet and does a pathway/raceway exist to access the closet?

A. All network connections for A/V equipment will be installed and patched by others

Q. Are speaker zones 1-6 existing? If so, does cabling related to these zones already exist at the lectern location where the new QSC amplifier is to be placed? If the cabling does not exist, is there a pathway/raceway from the lectern to the speaker zones?

A. Yes. Yes.

Q. Is there a pathway/raceway from the Roboshot 12E to the lectern where the One Bridge unit resides?

A. Yes.

Q. Is the projector mount existing? If so, what is the current projector model and or mount model?

A. One of the two existing mounts will be used. Chief VMC-91C

Q. Does a LSUHSC LAN drop exist at the projector?

A. A network connection to the NVX network switch will be installed for this project

Q. In order to size the lens, what is the screen size and distance from the projector to the screen?

Screen size: 141" x 87"

A. Distance from front of the current lens screen: 20.5 feet

Q. The specs for this project calls for one (1) Christie projector. The room presently has two (2).

1. Are you only changing out one (1)?

A. Yes, one projector will replace two. It will be centered and, using the windowing processor and the projector's scaling ability, we will overfill the current 2.5:1 screen to fill it in the center and when two images are displayed side by side

2. Does it have to be balanced to the existing unit?

A. No

3. What is the age of the existing unit?

A. N/A

4. Is the Vaddio camera a replacement or an addition?

A. Replacement

Q. In the programming notes, there is a reference to "Lighting Control". What equipment and control type will be required for this section? (RS232, DMX, CresNET)

A. Lighting presets are currently recalled by the control system via RS232; the replacement system will do the same

Q. Will the new projector be shooting onto an existing screen?

A. Yes.

Q. What size is the screen?

A. 141" x 87"

Q. Will the screen require control by the control system?

A. No, the screen is fixed

Q. If so, does the screen have a low voltage controller?

A. N/A

Q. How far is the projector to be from the screen?

A. 20.5 feet

Q. What is the ceiling type and height of the ceiling where the projector will be mounted?

A. Sheetrock fur down between open ceiling; 11.6 feet floor to ceiling

Q. Is the lectern mic existing on the OFE lectern or will this need to be provided and installed?

A. The mic is existing and will be OFE

Q. If we need to provide the lectern microphone, what make and model is desired?

A. N/A

Q. Are the speakers existing and already installed?

A. Yes.

Q. What is the count of speakers for each zone?

A. 2-4 speakers per zone; 22 speakers total

Q. Are the speakers already wired for each zone?

A. Yes

Q. During the Pre-Bid Meeting walk-thru there was 2 existing projectors. Will this be removed before the AV contractor preforms the project installation?

A. They will be removed before the A/V integrator begins work

Q. During the Pre-Bid Meeting walk-thru there was 1 existing large projection screen. Will this remain in place or be replaced? If replaced, please provide size of screen.

A. It will remain in place

Q. During the Pre-Bid Meeting walk-thru there was 1 existing Lectern. Will this be the OFE lectern to be re-used? If not, please provide Make/Model of lectern and whether it will contain an AV equipment rack? Will it be portable and require an umbilical cord for mobility?

A. Existing OFE lectern will be used

Q. During the Pre-Bid Meeting walk-thru there was 8 Ceiling Speakers. Will these be re-used in the new renovation?

A. There are actually 22 ceiling speakers arranged in six zones; they will all be reused

Q. Statement of Work AHSON LHA document Page 1 states “The integrator is responsible for providing specifications for power, data, conduit, and floor penetration(s)”. This appears to indicate there will be a new floor box in the Lecture Hall. Who is responsible for supplying the Floor Box? Please provide Make/ Model of Floor Box to determine AV connection panel(s).

A. There is no new floorbox

Q. Statement of Work AHSON LHA document Page 2 states “The lectern will house the following device: AV Bridge”. However, this device is not indicated in the “Parts-AHSON-LHA for Bid” document. Please provide Make/Model of AV Bridge.

A. Vaddio part number 999-99600-200 on the Parts List includes the OneLINK Bridge System; the OneLINK Bridge is what is being called out



Q. Statement of Work AHSON LHA document Page 2 indicates the lectern will house all the AV equipment. This equipment needs to be controlled vis the LAN system. This should all be connected to a Network Switch with the lectern. Can this be provided OFE. If not, please provide requirements for network switch.

A. Network connections will be provided inside of the lectern for all AV equipment that requires it, including NVX; no switches are to be provided by the integrator

Q. Statement of Work AHSON LHA document Page 2 states “The lectern will house the following device: HuddlePod Air2”. This device is typically used in conference room setting, can you describe how this device will be used?

A. This device must be provided by the integrator; LSUHNO will use it as needed

Q. Statement of Work AHSON LHA document Page 3 indicates the QSC Core 110F will have a Lectern Mic Input. However, this device is not indicated in the “Parts\_AHSON-LHA for Bid” document. Will this device be OFE? If not, please provide Make/Model of Lectern Mic.

A. The lectern microphone is OFE

Q. After reviewing the Statement of Work AHSON LHA document we noted there was no Assisted Listening System. Will this be required? If so, please provide requirements for ALS.

A. No ALS is required

Q. Please provide desired substantial completion date or preliminary project schedule if available.

A. To be determined.

Q. Is a bid bond required for this project? If yes, is there a specific form to use?

A. A bid bond is not required for this bid.

Q. Is a Payment & Performance Bond required for this project?

A. A payment & performance bond is not required for this project.

Q. Is this project subject to union labor or wages?

A. No.

Q. Is this project subject to prevailing wages? If so, please provide current wage rate table.

A. This project is not subject to prevailing wages.

Q. Is this project subject to liquidated damages? If so, what is the amount?

A. This project is not subject to liquidated damages.



Q. Will monthly progress payments be made? If so, when will they be due and what is the Retainage Percent?

A. Progress payments will not be made.

Q. Is this project subject to security or access badging?

A. Yes. Badges will be assigned prior to beginning work.

Q. Will onsite parking be provided for this project?

A. No parking will be provided. Street parking is available.

Michael D. Williams  
Purchasing

By \_\_\_\_\_ Name/Title \_\_\_\_\_  
(Signature) (Type or Print)

Firm's Name \_\_\_\_\_