



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

September 28, 2023

Please find the following addendum to the below mentioned BID.

Addendum No.: 2

Bid#: 23-3-2

Project Name: Cross Gates Water System New Elevated Storage Tanks

Bid Due Date: October 18, 2023

GENERAL INFORMATION:

1. Non-mandatory pre-bid was conducted on Tuesday, 9/26/23.
 - a. Sign-in sheet attached.
 - b. Attendees were reminded of the following provisions in the contract documents, and the requirements emphasized:
 - i. Cooperation with other contractors operating simultaneously on the Ozone Pines site is required.
 - ii. The Willow Wood site is constricted; existing well and hydropneumatic tank must remain in operation during tank construction, and the site is in a residential area. Pre-construction survey within the radius shown (inside & outside of structures) is required.
 - iii. Superintendence requirement will be enforced.
 - iv. Weather days are only awarded if Contractor intended to work and was prevented from working.
 - v. Contractor is required by electrical specifications to coordinate and pay all utility fees for new service, temporary service, or other requirements of the project.
2. Specification Section 08 “General Conditions”, para 11.03, **add** as last sentence of the paragraph, “*Failure to meet the intermediate performance period at the Willow Wood site shall require per diem payment of liquidated damages in the amount stated above.*”



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

3. Specification Section 11 “Federal Clauses”, **clarification**: Paragraph 2, Davis-Bacon Act, states “when required by Federal program legislation” Contractors shall comply with the Davis-Bacon Act. The State Grant Administering Agency advised Owner that compliance with Davis-Bacon Act **is not** required on this project.
4. Specification Section 02300 “Excavation and Backfill”, **add** Paragraph 3.09 “TESTING” as follows: *“Compaction tests shall be performed for each lift of bedding and backfill, at no less than one per 100 linear feet of trench. Re-testing for failed result shall be at no additional cost to the Owner.”*
5. Specification Section 02800 “Elevated Water Storage Tanks”, **add** paragraph 1.07 D. as follows *“Nominal changes to tank dimensions shown on the drawings will be considered. If such nominal changes are reasonable and do not adversely affect function of the system or operations, Owner may approve at Owner’s sole discretion. Approval will not be unreasonably withheld.”*
6. Specification Section 03300 “Cast in Place Concrete”
 - a. Paragraph 1.02 A.1a, **delete** “Owner will” and **replace** with “Contractor shall”
 - b. Paragraph 1.02 A.1b, **delete** “Owner’s” and **replace** with “Contractor’s”
 - c. Paragraph 1.02 A.2, **delete** “Owner’s” and **replace** with “Contractor’s”
 - d. **Delete** paragraph 2.02 H “Crystalline Waterproofing Admixture”. No waterproofing admixture is required.
7. Drawing Sheet 2, Coordination of Work, Ozone Pines, **add** *“Tank Contractor shall mobilize and drive piles immediately after pile driving completion at Willow Wood. Pile completion at Ozone Pines is required prior to well drilling.”*
8. Drawing Sheet 12, Tank Data Table **clarification**: “High Water Line (ft)” values are dimensions from top of foundation to overflow; meaning that the Willow Wood and Ozone Pines tanks require overflow 170 ft and 168 ft above top of foundation, respectively.
9. Drawing Sheet 16, “Process Schematic and Schedules” **clarification**: The Note *“Contractor to provide 2 – 150 lb chlorine gas cylinders for testing purposes.”* does not apply to this contract. Well Contractor is required to provide cylinders.



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

QUESTIONS & ANSWERS:

- Question: The Stratum Engineering geotechnical report provides design recommendations for H-Piles and Precast Concrete Piles. However, Spec 02800, "Elevated Water Storage Tank", Parts 1.06.C.1 and 2.03.A states that the piles must be H-Piles. Is the use of Precast Concrete Piles acceptable?
Answer: No.
- Question: Spec 02800, "Elevated Water Storage Tank", does not provide the design tank fill rate (in gpm). This fill rate is needed to confirm the adequacy of the specified 8" diameter overflow pipe. Please provide the design tank fill rate.
Answer: Willow Wood – 500gpm. Ozone Pines – 1000gpm.
- Question: Is there any 3rd party inspection (i.e. TIC, KLM, AEC, etc.) on engineering construction or painting? If so, who will it be and on what portion of work?
Answer: Yes. In addition to the other inspections and testing by independent testing laboratory at Contractor cost, as required by the contract documents, Owner will employ at Owner's cost KGC Environmental to perform coating audits.

ATTACHMENTS:

Pre-Bid Sign in Sheet

<< End of Addendum 2 >>



St. Tammany Parish, Department of Utilities

SIGN-IN SHEET

Pre-Bid, Bid No 23-3-2
Cross Gates Water System
New Elevated Storage Tank

LOCATION: 21454 Koop Dr. Mandeville, LA 70471, 3rd Floor Staff Conference Room

DATE & TIME: 9/26/2023 ; 9:00-10:00

NAME	REPRESENTING	TELEPHONE	E-MAIL ADDRESS
Bob Moerian	STPGov. / DU	893-1717	Bmoerian@STPGov.org
Ethan Veljovic	Wolf Group Const (Subcont)	504-715-8615	wolfgroupconstruction@gmail.com
Adam Houck	CRSI	346-422-8627	adam.Houck@mcdermott.com
Chris Tissue	STPG Dept. of Utilities	(985)893-1717	cptissue@stpgov.org
ANDRE MONNOT	PRINCIPAL ENGINEERING	985 624 5001	ANDRE@PI-AEC.COM
Rachel Forehand	STPGOV / Procurement	985 898 2520	rforehand@stpgov.org
Thelma Naguib	" "	" "	tnaguib@STPGOV.ORG
Shelley Speed	STPG Grants	(985)867-5095	slspeed@stpgov.org
ANDREW HONTIVEROS	STP-DU	(985)893-1717	andhontiveros@stpgov.org
TOM SCHREINER	PRINCIPAL EKV	624-5001	tom@PI-AEC.COM